







RVINS OF THE PALACE
OF THE EMPEROR DIOCLETIAN
AT SPALATRO IN DALMATIA
BY R. ADAM F.R.S F.S.A
ARCHITECT TO THE KING
AND TO THE QVEEN
London
PRINTED FOR THE AVTHOR
MDCCLXIIII

14. ¹⁴/₇

NA
320
A5
Case 5

THE PALACE
OF THE EMPEROR
AT THE
BY THE
KING
AND
FOR THE
MOUNTAIN

T O

T H E K I N G.

I Beg Leave to lay before your Majesty the RUINS of SPALATRO, once the favorite Residence of a great Emperor, who, by his Munificence and Example, revived the Study of Architecture, and excited the Masters of that Art to emulate in their Works the Elegance and Purity of a better Age.

ALL the Arts flourish under Princes who are endowed with Genius, as well as possessed of Power. Architecture in a particular Manner depends upon the Patronage of the Great, as they alone are able to execute what the Artist plans. Your Majesty's early Application to the Study of this Art, the extensive Knowledge you have acquired of its Principles, encourages every Lover of his Profession to hope that he shall find in GEORGE THE THIRD, not only a powerful Patron, but a skilful Judge.

a

AT

AT this happy Period, when Great Britain enjoys in Peace the Reputation and Power she has acquired by Arms, Your Majesty's singular Attention to the Arts of Elegance, promises an Age of Perfection that will compleat the Glories of your Reign, and fix an *Æra* no less remarkable than that of PERICLES, AUGUSTUS, or the MEDICIS.

I am,

May it please Your MAJESTY,

Your MAJESTY's

Most Dutiful Servant, and Faithful Subject,

ROBERT ADAM.

LIST OF SUBSCRIBERS.

THE KING

THE QUEEN

Her Royal Highness The Princess Dowager of Wales

His Royal Highness The Duke of York

His Royal Highness Prince William

His Royal Highness Prince Henry

A.

His Grace Archibald, Duke of Argyll 2 Setts
 Her Grace Jane, Dutches of Athol
 His Grace Peregrine, Duke of Ancaster
 The Right Honorable George, Earl of Albemarle
 The Right Honorable James, Earl of Abercorn
 The Right Honorable Heneage, Earl of Aylesford
 The Right Honorable, John Earl of Ashburnham
 The Right Honorable William, Earl of Ancram
 The Right Honorable George, Lord Anfon
 Lieutenant General Abercrombie
 William Adair, Esq;
 John Adam, Esq; Architect, of Edinburgh
 James Adam, Esq; Architect
 William Adam, Esq;
 William Aisleby, Esq;
 Claudius Amyand, Esq;
 Mr. Saffron Alken, Carver
 Ralph Allen, Esq;
 Mr. James Arrow

B.

His Grace Henry, Duke of Buccleugh
 The Right Honorable John, Earl of Bute 10 Setts
 The Right Honorable William, Earl of Bath
 The Right Honorable William, Lord Viscount Barrington.
 The Right Honorable Frederick, Lord Baltimore
 The Right Honorable Lady Caroline Burdett
 William Baird, of Newbyth, jun. Esq;
 Mr. John Balfour, Bookfeller 6 Setts
 Isaac Barré, Esq;

Lieutenant Colonel Bathurst
 Captain William Bayne, of the Navy
 John Bayne, Esq;
 Henry Beauclercq, Esq;
 Major General Beckwith
 William Beckwith, Esq;
 The Honorable Sir Harry Bellenden, late Gentleman
 Usher of the Black Rod
 Robert Berry, Esq;
 The Rev. John Blair, L. L. D. Prebendary of Westminster, F. R. S. and F. S. A.
 Patrick Blair, M. D. of Cork
 William Blair, Esq; Clerk of the Privy Council
 Sir Walter Blackett, Baronet
 Lieutenant General Bland
 Mrs. Bland
 The Right Honorable Admiral Boscawen 2 Setts
 Mrs. Boscawen 2 Setts
 Edward Hugh Boscawen, Esq; 2 Setts
 Thomas Bradshaw, Esq;
 Lieutenant Colonel James Bramham, Engineer
 Thomas Brand, Esq; of the Hoo
 Richard Brockelsby, M. D. and F. R. S. Physician
 to the Army
 Lieutenant Colonel Brome
 Colonel Browne
 The Honorable and Rev. James Bruce
 The Honorable Major Thomas Bruce
 Mr. Alexander Bruce
 Henry Bullock, Esq;
 Mr. John Burges, Carpenter
 Mr. James Burgh, of Newington

a

Lieute-

LIST OF SUBSCRIBERS.

Lieutenant Colonel Burton
 Thomas Burton, Esq;
 Dr. George Buxton

C.

The Most Honorable James, Marquis of Carnarvon
 The Right Honorable Philip, Earl of Chesterfield
 The Right Honorable George, Earl of Cardigan
 The Right Honorable George, Earl of Coventry
 The Right Honorable John, Earl of Cassils
 The Right Honorable Charles, Earl Cornwallis
 The Right Honorable Lord Frederick Cavendish
 The Right Honorable Lord Frederick Campbell
 The Right Honorable William Lord Viscount Courtenay
 The Right Honorable Hugh, Lord Clifford
 The Right Honorable Robert, Lord Clive
 The Honorable Lieutenant General Conway
 Thomas Calderwood, of Polton, Esq;
 James Campbell, of Ardkinglas, Esq;
 Daniel Campbell, of Shawfield, Esq;
 Alexander Campbell, Esq, of Grenada
 Mr. Benjamin Carter, Statuary
 Nathaniel Castleton, Esq;
 Major General Julius Cæsar
 Mr. George Chalmers, of Edinburgh, Merchant
 Robert Chalmers, Esq;
 Rice Charlton, M. D. of Bath
 James Cheap, of Sauchie, Esq;
 Francis Child, Esq;
 Mrs. Cholmondely, of Clarges Street,
 Mr. Thomas Churchill
 John Chute, Esq;
 William Clayton, Esq; of Hawleyford, Buckinghamshire
 Sir James Clerk, Baronet
 Colonel Robert Clerk
 John Clerk, Esq;
 David Clerk, M. D. of Edinburgh
 John Cleveland, Esq;
 Mr. William Cobbett
 Archibald Cochran, Esq;
 Sir James Cockburn, Baronet
 Sir George Colebrook, Baronet
 Sir Charles Coote, Knight of the Bath
 Oliver Coult, Esq;
 Richard Combe, Esq;
 — Cooper, Esq; of the Temple
 Richard Cox, Esq;

William Crichton, Esq;
 Mrs. Cuninghame, of Enterkin
 Sir Ellis Cunliffe, Baronet
 William Cunynghame, of Craigends, Esq;
 Lady Curzon

D

His Grace William, Duke of Devonshire
 The Right Honorable Basil, Earl of Denbigh
 The Right Honorable William, Earl of Dumfries and Stair
 The Right Honorable William, Earl of Dunmore
 The Right Honorable William, Earl of Dartmouth
 The Right Honorable John, Earl of Darley
 The Honorable and Right Reverend Dr. Richard Trevor, Lord Bishop of Durham
 The Right Honorable Henry, Lord Digby
 The Right Honorable James, Lord Delford
 The Right Honorable —, Lord Dunkellin
 Henry Dagge, Esq;
 Richard Dalton, Esq; Librarian to his Majesty
 Sir Hugh Dalrymple, Baronet
 John Dalrymple, of Cranston, Esq;
 Hugh Dalrymple, of Fording, Esq;
 Captain James Dalrymple
 Mr. John Davidson, Clerk to the Signet
 James Dawkins, Esq;
 Sir Edward Deering, Baronet
 Mr. Dickson
 Thomas Dickson, M. D. Physician to St. Thomas's Hospital
 Peter Delmé, Esq;
 George Dempster, Esq;
 James Dewar, of Vogrie, Esq;
 Mr. Robert Doddsley
 Christopher D'Oyly, Esq;
 William Drake, Esq;
 Adam Drummond, Esq;
 John Drummond, Esq;
 Robert Drummond, Esq;
 Henry Drummond, Esq;
 The Rev. Mr. John Drysdale
 Matthew Duane, Esq; F. R. S.
 H. Duane, Esq;
 J. Duncan, D. D. Fellow of St. John's College, Oxford
 Sir Lawrence Dundas, Baronet
 Lady Dundas

Thomas

L I S T O F S U B S C R I B E R S .

Thomas Dundas, Esq;
Captain David Dundas

E.

The Right Honorable Brownlow, Earl of Exeter
The Right Honorable James, Earl of Errol
The Right Honorable Charles, Earl of Elgin and Kin-
cardin
The Right Honorable Patrick, Lord Elibank
The Right Honorable Welbore Ellis, Secretary at War
The Right Honorable Gilbert Elliot
The Right Honorable Charles Erskine, late Lord Jus-
tice Clerk
William Rawlinson Earle, Esq;
Colonel James Edmonston
Major General Elliot
William Elliott, of Wells, Esq;
Sir Harry Erskine, Baronet
Lady Erskine
Sir William Erskine

F.

The Right Honorable James, Earl of Findlater and Seafield
The Right Honorable James, Earl Fife
The Right Honorable Thomas Lord Foley
The Honorable Thomas Fitzmaurice
The Honorable Stephen Fox
The Honorable Archibald Fraser
Adam Fairholme, Esq;
Thomas Fairholme, Esq;
Lieutenant Colonel Faucitt
Sir Adam Ferguson, Baronet
Mr. Professor Adam Ferguson
John Forbes, Esq;
John Fordyce, of Aytoun, Esq;
Andrew Fletcher, Esq; one of the Senators of the Col-
lege of Justice
Frederick Frankland, Esq;

G.

His Grace Augustus, Duke of Grafton
Her Grace the Dutchess of Gordon
The Most Noble John, Marquis of Granby
The Right Honorable John, Earl of Granville
The Right Honorable Alexander, Earl of Galloway
The Right Honorable Thomas Lord Grantham
The Right Reverend Dr. William Warburton, Lord
Bishop of Gloucester

The Right Honorable George Grenville
The Right Honorable James Grenville
Samuel Garbett, Esq;
David Garrick, Esq;
Sir Alexander Gilmour, Baronet
Samson Gideon, Esq;
Reverend Mr. Charles Godwyn
James Gordon, Esq;
James Gordon, of Ellan, Esq;
Mr. John Gordon, at Lisbon, Merchant
Mr. Joseph Gordon
John Graham, of Dugaldstone, Esq;
Sir Ludowick Grant, Baronet
Mr. Baron Grant
Colonel James Grant, Governor of East Florida
James Grant, of Grant, Esq;
Andrew Grant, Esq;
The Abbot Grant, at Rome
— Grant, M. D.
Captain Richard Grenville
General Græme, Commander in Chief of the Vene-
tian Forces
Colonel David Græme, Secretary to the Queen
Sir James Gray, Knight of the Bath 2 Setts
Colonel George Gray
Sir John Griffin Griffin, Knight of the Bath
Lieutenant General John Guife, F. R. S.
Mr. Gwyn, Architect

H.

The Right Honorable Robert Lord Henley, Lord High
Chancellor of Great Britain
The Right Honorable Robert, Earl of Holderness
The Right Honorable John, Earl of Hopetoun 5 Setts
The Right Honorable Francis, Earl of Hertford
The Right Honorable Philip, Earl of Hardwicke
The Right Honorable Lord Charles Hay
The Right Honorable Lady Mary Hume
The Right Honorable Charles Lord Hope
The Right Honorable Henry Lord Holland
The Honorable Charles Hope Weir 3 Setts
The Honorable James Hope
The Honorable Robert Harley
The Honorable Charles Hamilton
The Honorable William Hamilton
The Honorable Mr. Howard
John Hamilton, of Bargeney, Esq;
Major James Hamilton

b

Lieute-

LIST OF SUBSCRIBERS.

Lieutenant Colonel Charles O'Harra
 James Harris, Esq; one of the Lords Commissioners of
 the Admiralty, F. R. S.
 Colonel Harvey, Adjutant General
 George Hay, L. L. D. one of the Lords Commissioners
 of the Admiralty
 Lieutenant Colonel Thomas Hay
 Sir Gilbert Heathcote, Baronet
 Christopher Hervey, Esq;
 Sir Rowland Hill, Baronet
 Richard Hill, Esq;
 Mr. John Hobcraft
 Lieutenant Colonel Hotham
 George Home, Esq;
 John Home, Esq;
 Thomas Hollis, Esq; F. R. S. F. S. A.
 Francis Holburne, Esq; Vice Admiral of the Red
 John Hope, Esq;
 Archibald Hope, Esq;
 John Hope, Esq; of Amsterdam
 John Hort, Esq;
 Colonel Hotham
 Lieutenant General Howard
 George Hungerford, Esq;
 William Hunter, M. D. Physician to the Queen
 Alexander Hume, Esq;
 Abraham Hume, Esq;
 David Hume, Esq;

I.

Charles Jenkinson, Esq;
 Mrs. Johnston
 George Johnston, Esq; Governor of West Florida
 Alexander Johnston, of Garsfalloch, Esq;
 Mr. Andrew Johnston
 Mr. William Innes

K.

His Grace Evelyn, Duke of Kingston
 The Right Honorable Thomas, Earl of Kinnoul
 The Honorable Colonel Keppel
 George Keate, Esq;
 Lieutenant Colonel Keith
 Joshua Kirby, Esq; Designer in Perspective to his Ma-
 jesty
 David Kinloch, Esq;
 Sir Wyndham Knatchbull, Baronet

L.

His Grace Thomas, Duke of Leeds
 Her Grace the Dutchess Dowager of Leeds
 The Most Honorable John, Marquis of Lorn
 The Right Honorable Henry, Earl of Lincoln
 The Right Honorable Lord George Lenox
 Field Marshal John Lord Viscount Ligonier
 The Right Honorable George Lord Lyttelton
 The Right Honorable Lady Lindores
 — Lacy, Esq;
 Edwin Lafcelles, Esq;
 Daniel Lafcelles, Esq;
 Edward Lafcelles, Esq;
 Mr. Peter Lawfon
 Mr. Stiff, Leadbetter
 Captain John Lindsay, of the Navy
 Mr. John Linnell
 Alexander Littlejohn, of Woodfoun, Esq;
 William Locke, Esq;
 John Lockhart, of Lee, Esq;
 Charles Lowth, Esq;
 Sir James Lowther, Baronet 3 Setts
 Library of the Faculty of Advocates, at Edinburgh
 Library of the University of Glasgow
 Library of Oriel College, Oxford

M.

His Grace George, Duke of Marlborough
 His Grace William, Duke of Montrose 2 Setts
 Her Grace the Dutchess of Montrose
 His Grace George, Duke of Manchester
 The Right Honorable James, Earl of Morton, F. R. S.
 The Right Honorable James, Earl of Moray
 The Right Honorable James, Earl of March and
 Ruglen
 The Right Honorable Lord James Manners
 The Right Honorable Lord William Manners
 The Right Honorable William Lord Mansfield, Lord
 Chief Justice of England
 The Right Honorable Lord Montague
 The Right Honorable James Stewart Mackenzie, Lord
 Privy Seal of Scotland
 The Honorable Mr. Baron Maule
 William Macdowal, of Castle Semple, Esq;
 John Mackay, Esq; of Bellfields
 William Mackenzie, Esq;
 2 Setts Edward Marjoribanks, Esq;

James

LIST OF SUBSCRIBERS.

James Macpherfon, Esq;

Robert Malcolm, Esq;

Sir William Mayne, Baronet

Robert Mayne, Esq;

Lewis Mendes, Esq;

Paul Methuen, Esq;

Mr. George Mercer, jun.

John Milbanke, Esq;

Mr. Andrew Millar, Bookseller

John Monro, M. D.

Edward Montagu, Esq;

Mrs. Montagu

William Morehead, Esq;

James Morris, Esq;

—— Morit, Esq; Dean Street, Soho

Mr. James Mofs, Joiner to his Majesty

Sir Roger Mostyn, Baronet

Mr. Baron Muir

Hutchinson Mure, Esq;

John Murray, of Philiphaugh, Esq;

Alexander Murray, jun. of Murrayfield, Esq;

James Murray, of Abercainry, Esq;

James Mytton, Esq;

N.

His Grace Edward, Duke of Norfolk

His Grace Thomas, Duke of Newcastle

The Right Honorable Charles, Earl of Northampton

The Right Honorable Ann, Countess of Northampton

The Right Honorable Hugh, Earl of Northumberland

The Right Honorable the Countess of Northumberland

Lieutenant General Napier

Arnold Nesbit, Esq;

Houston Stewart Nicolson, Esq;

Mr. Samuel Norman

Mr. Robert Norrie, Painter

O.

The Right Honorable George, Earl of Orford

The Right Honorable James Oswald

John Offley, Esq;

James Ord, Esq;

John Orr, of Barrowfield, Esq;

Richard Oswald, Esq;

Mr. Oxley, of Ripon, in Yorkshire

P.

His Grace William Duke of Portland

His Grace Henry, Duke of Portland

The Right Honorable Henry, Earl of Pembroke and Montgomery

The Right Honorable Other Lewis, Earl of Plymouth

The Right Honorable Charles, Earl of Portmore

The Right Honorable William, Earl of Panmure

The Right Honorable the Countess of Pomfret

The Right Honorable John Lord Pollington

5 Setts

John Parker, Esq;

Richard Pennant, Esq;

Lieutenant Colonel Philips

Colonel William Pitt

Thomas Pitt, Esq; one of the Lords Commissioners of the Admiralty

The Rev. Dr. Plumtre

2 Setts

Mr. John Pratt

Robert Price, Esq;

Uvedale Price, Esq;

Andrew Pringle, Esq; one of the Senators of the College of Justice

John Pringle, M. D. F. R. S. Physician to the Queen

Thomas Proufe, Esq;

Q.

His Grace Charles Duke of Queensberry

Her Grace the Dutchess of Queensberry

R.

His Grace Charles, Duke of Richmond and Lenox

His Grace John, Duke of Rutland

Her Grace the Dutchess Dowager of Roxburgh

The Most Noble Charles, Marquis of Rockingham

The Right Honorable Neil, Earl of Roseberry

The Right Honorable Philip Lord Viscount Royston 2 Setts

The Honorable Thomas Robinson

The Right Honorable Richard Rigby

Allan Ramsay, Esq; Painter to his Majesty

Matthew Raper, Esq; F. R. S. F. S. A

Joshua Reynolds, Esq; F. R. S.

William Robertson, D. D. Principal of the University of Edinburgh

Colonel James Robertson

Mr. Archibald Robertson

c

Mr.

LIST OF SUBSCRIBERS.

- Mr. Patrick Robertson
 Charles Rogers, Esq; F. R. S. F. S. A.
 Sir Thomas Robinson, Baronet, F. R. S.
 Sir George Bridges Rodney, Baronet
 Robert Roper, Esq;
 Mr. Joseph Rose
 George Rose, Esq;
 Thomas Rowley, Esq;
 Captain Clotworthy Rowley
 Lieutenant Colonel Roy
 Nathaniel Ryder, Esq;
 Mr. Michael Rysbrack, Statuary
- S.
- The Right Honorable Henry, Earl of Suffolk and Berkshire
 The Right Honorable William, Earl of Sutherland
 The Right Honorable William Earl of Stirling
 The Right Honorable Philip, Earl Stanhope 2 Setts
 The Right Honorable William, Earl of Shelburne 5 Setts
 The Right Honorable Lord Robert Sutton
 The Right Honorable Lord George Sutton
 The Right Honorable John Lord Viscount Spencer
 The Right Honorable Nathaniel Lord Scarisdale
 The Right Honorable Hans Stanley, one of the Lords Commissioners of the Admiralty
 The Honorable Sir William Stanhope, Knight of the Bath
 The Honorable James Stewart
 The Honorable General James St. Clair
 John Sargent, Esq; of May Place
 Sir George Saville, Baronet, F. R. S.
 Joseph Salvador, Esq; F. R. S.
 Mr. James Scott, at Edinburgh, Merchant
 Major General Skinner, chief Engineer
 Mr. Alexander Small, Surgeon
 The Rev. Mr. Edward Smallwell, B. D. Student of Christ Church
 Joseph Smith, Esq; at Venice
 James Smollet, of Bonhill, Esq;
 The Honorable Mrs. Southwell
 Mr. John Spencer, Carpenter
 George Stevens, Esq;
 Dr. Alexander Stevenson, Physician at Glasgow
 Andrew Stewart, Esq;
 John Stewart, Esq;
 Robert Stewart, Esq;
 Andrew Stone, Esq;
- The Rev. Mr. Storrer
 Colton Stow, Esq;
 6 Setts Mr. William Strahan, Printer
 James Stuart, Esq; F. R. S. F. S. A.
 John Symonds, Esq;
- T.
- The Most Honorable John, Marquis of Tweeddale
 The Most Honorable the Marchioness of Tweeddale
 The Most Honorable Francis, Marquis of Tavistock
 The Right Honorable Richard Earl Temple
 The Right Honorable the Countess of Talbot
 The Right Honorable Lady Townshend
 The Right Honorable Major General George Townshend
 The Right Honorable Charles Townshend
 Peter Taylor, Esq;
 Paris Taylor, Esq;
 Thomas Thorowton, Esq;
 Lieutenant Colonel Henry Townshend
 Henry Tuckfield, Esq;
 Marmaduke Tunstale, Esq;
 John Turton, M. D. F. R. S.
 Mr. William Tyler, Sculptor
- U.
- The Right Honorable Ralph Earl Verney
 The Honourable Wilmot Vaughan
 Francis de Valengin, M. D.
 Alexander Udny, of that Ilk, Esq;
 Robert Udny, Esq;
 Henry Uthoff, Esq;
 Clotworthy Upton, Esq;
- 2 Setts
- W.
- The Right Honorable John, Earl of Westmoreland
 The Right Honorable John, Earl Wakegrave
 The Right Honorable Francis, Earl of Warwick
 The Right Honorable Hugh Lord Viscount Warkworth
 The Right Honorable John Lord Willoughby de Broke
 The Right Honorable Edward Lord Winterton
 The Honorable James Weymss
 The Honorable Horace Walpole
 Sir George Warren, Knight of the Bath
 William Wallace, jun. Esq; Advocate
 Major General Watton
 Lieutenant Colonel Watton
 Sir John Webb, Bart.

Richmond

LIST OF SUBSCRIBERS.

Richmond Webb, Esq;		Sir Thomas Wilson
Philip Carteret Webb, Esq; F. R. S.	2 Setts	John Winter, Esq;
Mr. William Webley		Robert Wood, Esq;
Mr. Henry Webley, Bookfeller		James Wright, Esq;
Alexander Wedderburn, Esq;		— Wynn, Esq;
Lieutenant Colonel David Wedderburn		Mr. Samuel Wyatt
Edward Weston, Esq;		John Wyndham Bowyer, Esq;
Thomas Whately, Esq;		
Mr. Edward Whatmore, of Salisbury		Y:
Sir John Whitefoord, of Whitefoord, Baronet		His Grace Robert, Lord Archbishop of York
Sir John Whitefoord, of Blahan, Baronet		The Honorable Sir Joseph Yorke, Knight of the Bath
Allan Whitefoord, of Ballomyle, Esq;		The Honorable Charles Yorke 2 Setts
Robert Whytt, M. D. Professor of Medicine, in the		The Honorable John Yorke
University of Edinburgh, F. R. S.		Captain Young, of the 33d. Regiment of Foot
Israel Wilkes, Esq; F. R. S.		

FOREIGN SUBSCRIBERS.

Sua Altezza Reale L'Infante Duca di Parma, &c.	Il Sign. Conté Girolamo del Pozzo dá Verona
Sua Altezza Serenissima Loredan il Doggio di Venezia	Il Sign. Conté Alessandro Pompei
Sua Eccellenza il Signore de Tilloe Ministro del Duca di Parma	Il Sign. Conté Antonio Marcovich
La Libreria di San Marco di Venezia	Il Sign. Torelli dá Verona
Girolamo Afcario Guistinian Nobile Veneto Cavalier della Stola D'Oro ed Ambasciadore á Roma	Il Sign. Capitano Pietro Craina
Andrea Querini Nobile Veneto e Senatore	Il Sign. Gio. Bab. Piranesi Architetto Veneto F. S. A. in Londra
Angelo Querini Nobile Veneto ed Avagador de Commun	Il Sign. Antonio Zucchi pittore dá Venezia
Vicenza di Riva Nobile Veneto e Senatore	Il Sign. Davido Fossati pittore dá Venezia
Polo Renier Nobile Veneto e Savio del Consiglio	Monf. Le Norment, Fermeir General du Roy et Ad- ministrateur General des postes de France
Gio. Dom. Tiepolo Nob. Veneto ed Ambasciadore in Francia	Monf. Charles Louis Clerisseau
Filippo Farfetti Nobile Veneto	Monf. Monginot de Versailles
Il Sign. Conte Francesco Algarotti Ciambelano di S. M. Il Re di Prussia, e Cavalier del Ordine del Merito	Monf. du Vivier, Graveur des Medailles du Roy, á Paris
Il Sign. Conté Zanetti dá Venezia	Mr. John Enschede, Letter Founder and Printer, at Haer- lem, in Holland.

INTRODUCTION.

THE buildings of the Ancients are in Architecture, what the works of Nature are with respect to the other Arts ; they serve as models which we should imitate, and as standards by which we ought to judge: for this reason, they who aim at eminence, either in the knowledge or in practice of Architecture, find it necessary to view with their own eyes the works of the Ancients which remain, that they may catch from them those ideas of grandeur and beauty, which nothing, perhaps, but such an observation can suggest.

Scarce any monuments now remain of Grecian or of Roman magnificence but public buildings. Temples, amphitheatres, and baths, are the only works which had grandeur and solidity enough to resist the injuries of time, and to defy the violence of barbarians: the private but splendid edifices in which the citizens of Athens and of Rome resided, have all perished ; few vestiges remain of those innumerable villas with which Italy was crowded, though in erecting and adorning them the Romans lavished the wealth and spoils of the world. Some accidental allusions in the ancient poets, some occasional descriptions in their historians, convey such ideas of the magnificence, both of their houses in town and of their villas, as astonish an artist of the present age. The more accurate accounts of these buildings, which we find in Vitruvius and Pliny, confirm this idea, and convince us, that the most admired efforts of modern Architecture, are far inferior to these superb works, either in grandeur or in elegance. There is not any misfortune which an Architect is more apt to regret than the destruction of these buildings, nor could any thing more sensibly gratify his curiosity, or improve his taste, than to have an opportunity of viewing the private edifices of the Ancients, and of collecting, from his own observation, such ideas concerning the disposition, the form, the ornaments, and uses of the several apartments, as no description can supply.

This thought often occurred to me during my residence in Italy ; nor could I help considering my knowledge of Architecture as imperfect, unless I should be able to add the observation of a private edifice of the Ancients to my study

B

of

of their public works. This led me to form the scheme of visiting the Ruins of the Emperor DIOCLESIAN's Palace at Spalatro, in Dalmatia; that favorite building, in which, after resigning the empire, he chose to reside. I knew, from the accounts of former travellers, that the remains of this palace, though tolerably entire, had never been observed with any accuracy, or drawn with any taste; I was no stranger to the passion of that prince for Architecture, which prompted him to erect many grand and expensive structures at Rome, Nicomedia, Milan, Palmyra, and other places in his dominions; I had viewed his public baths at Rome, one of the noblest, as well as most entire, of all the ancient buildings, with no less admiration than care; I was convinced, notwithstanding the visible decline of Architecture, as well as of the other arts, before the reign of DIOCLESIAN*, that his munificence had revived a taste in Architecture superior to that of his own times, and had formed artists capable of imitating, with no inconsiderable success, the style and manner of a purer age. The names and history of those great masters are now unknown, but their works which remain, merit the highest applause; and the extent and fertility of their genius, seem to have equalled the magnificence of the monarch by whom they were employed.

Induced by all these circumstances, I undertook my voyage to Dalmatia with the most sanguine hopes, and flattered myself that it would be attended not only with instruction to myself, but might produce entertainment to the public.

Having prevailed on Mr. Clerisseau, a French artist, from whose taste and knowledge of antiquities I was certain of receiving great assistance in the execution of my scheme, to accompany me in this expedition, and having engaged two draughtsmen, of whose skill and accuracy I had long experience, we set sail from Venice on the 11th of July, 1757, and on the 22d of that month arrived at Spalatro.

This city, though of no great extent, is so happily situated, that it appears, when viewed from the sea, not only picturesque but magnificent. As we entered a grand bay, and sailed slowly towards the harbour, the Marine Wall,

* DIOCLESIAN began his reign An. Dom. 284. He resigned the empire in the year 304, and died in the year 313; having spent the last nine years of his life at Spalatro,

and long Arcades of the Palace, one of the ancient Temples, and other parts of that building which was the object of our voyage, presented themselves to our view, and flattered me, from this first prospect, that my labor in visiting it would be amply rewarded.

To these soothing expectations of the pleasure of my task, the certain knowledge of its difficulty soon succeeded. The inhabitants of Spalatro have destroyed some parts of the palace, in order to procure materials for building; and to this their town owes its name, which is evidently a corruption of Palatium. * In other places houses are built upon the old foundations, and modern works are so intermingled with the ancient, as to be scarcely distinguishable: assiduity, however, and repeated observation, enabled me to surmount these difficulties. Attention to such parts of the palace as were entire, conducted me with certainty to the knowledge of those which were more ruinous; and I was proceeding in my work with all the success I could have expected, when I was interrupted by an unforeseen accident.

The Venetian governor of Spalatro, unaccustomed to such visits of curiosity from strangers, began to conceive unfavorable sentiments of my intentions, and to suspect that under pretence of taking views and plans of the Palace, I was really employed in surveying the state of the fortifications. An order from the Senate to allow me to carry on my operations, the promise of which I had procured at Venice, had not yet arrived; and the governor sent an officer commanding me to desist. By good fortune General Græme, commander in chief of the Venetian forces, happened at that time to be at Spalatro on the service of the State. He interposed in my behalf, with the humanity and zeal natural to a polite man, and to a lover of the Arts, and being warmly seconded by Count Antonio Marcovich, a native of that country, and an officer of rank in the Venetian service, who has applied himself with great success to the study of Antiquities, they prevailed on the governor to withdraw his prohibition, though, by way of precaution, he appointed an officer constantly to attend me. The fear of a second interruption added to my industry, and, by unwearied application during five weeks, we completed, with an accuracy that afforded me great satisfaction, those parts of our work which it was necessary to execute on the spot.

C

Encouraged

Encouraged by the favorable réception which has been given of late to works of this kind, particularly to the Ruins of Palmyra and Balbec, I now present the fruits of my labor to the public. I am far from comparing my undertaking with that of Messieurs Dawkins, Bouverie, and Wood, one of the most splendid and liberal that was ever attempted by private persons. I was not, like these gentlemen, obliged to traverse deserts, or to expose myself to the insults of barbarians; nor can the remains of a single Palace vie with those surprising and almost unknown monuments of sequestered grandeur which they have brought to light; but at a time when the admiration of the Grecian and Roman Architecture has risen to such a height in Britain, as to banish in a great measure all fantastic and frivolous tastes, and to make it necessary for every Architect to study and to imitate the ancient manner, I flatter myself that this work, executed at considerable expence, the effect of great labor and perseverance, and which contains the only full and accurate Designs that have hitherto been published of any private Edifice of the Ancients, will be received with indulgence, and may, perhaps, be esteemed an acquisition of some importance.

A
D E S C R I P T I O N
O F T H E
G E N E R A L P L A N
O F
D I O C L E S I A N ' s P A L A C E
A S R E S T O R E D ,

E X P L A I N I N G

The Manner of disposing the Apartments in the Houses of the Ancients.

THE Palace of DIOCLESIAN at Spalatro possessed all those advantages of situation, to which the Ancients were most attentive, and which they reckoned essential to every agreeable villa. The soil of that part of Illyricum was dry and fertile, though now considerable tracts of land lie uncultivated. The air is pure and wholesome; and though extremely hot during the summer months, this country seldom feels those sultry and noxious winds to which the coast of Istria, and some parts of Italy, are exposed. By the care of the architect in observing an excellent precept of Vitruvius (1), every inconvenience arising from the winds is avoided as far as possible; the principal streets or apertures of the villa being so disposed, as not to lie open to the impression of any of the winds which blow most frequently in this climate. The views from the palace are no less beautiful, than the soil and climate were inviting. Towards the West lies the fertile shore that stretches along the Adriatic, in which a number of small islands are scattered in such a manner, as

(1) Vitruvius, L. 1. C. 4 and 6. L. 6. C. 1;

to give this part of the sea the appearance of a great lake. On the North West lies the bay which led towards the ancient city of Salona, and the country beyond it appearing in sight, forms a proper contrast to that more extensive prospect of water which the Adriatic presents both to the South and to the East. Towards the North the view is terminated by high and irregular mountains, situated at a proper distance, and in many places covered with villages, woods, and vineyards.

From this description, as well as from the views which I have published, (Plates 3d and 4th) it is evident that no province in this wide-extended empire, could have afforded DIOCLESIAN a more elegant place of retirement; and the beauty of the situation, no less than the circumstance of its being his native country, seems to have determined him to fix his residence there.

The only thing wanting at Spalatro was good water; but this defect was supplied by an aqueduct from Salona, (Plate 61) several arches of which remain at present, and the conduit that formerly conveyed the water is still visible.

The palace itself was a work so great, that the Emperor Constantine Porphyrogenitus, who had seen the most splendid buildings of the Ancients (1), affirms that no plan or description can convey a perfect idea of its magnificence. The vast extent of ground which it occupied is surprising at first sight; the dimensions of one side of the quadrangle, including the towers, being no less than 698 feet, and of the other 592 feet, making the superficial content 413216 feet, being nearly nine and an half English acres. But when we consider that it contained proper apartments not only for the Emperor himself, and for the numerous retinue of officers who attended his court, but likewise edifices and open spaces for exercises of different kinds; that it was capable of lodging a pretorian cohort, and that two temples were erected within its precincts, we will not conclude the area to have been too large for such a variety of buildings.

(1) *Const. Porphyrogenitus de Administrando Imperio ad Romanum Filium.*

The present state of this great structure may be more perfectly conceived, by considering the Plan of it, (Plate 5) than by any description whatever. The curiosity of the reader, however, will not be satisfied with viewing this building in its present ruinous condition, but must naturally desire to form some idea of what was its plan and disposition in its more perfect state. By good fortune its remains are, in many places, so entire, as to be able to fix, with the utmost certainty, the form and dimensions of the principal apartments. The knowledge of these, leads to the discovery of the corresponding parts; and the descriptions given us by Pliny (1) and Vitruvius (2) of the Roman villas, enable us to assign to each apartment its proper name, and to discover its use. The manners and domestic life of the Ancients differed so widely from ours, that their ideas, with regard to what was necessary or ornamental in a dwelling house must likewise have been extremely different.

The whole building was of a quadrangular form, (Plate 6) and was divided by two large streets, leading to the different gates, and crossing each other at right angles.

The principal street which we enter from the North, is 36 feet 3 inches in breadth: its length, from the inside of the gate to the place where it intersects the street which runs from East to West, is 238 feet 5½ inches; the breadth of the other street is the same, and it extends 424 feet 6 inches. Both of them are bounded on each side by Arcades of 13 feet wide, many of which are still entire. The first of these streets leads directly to the Peristylum (A), which was the name the Ancients gave to the area or court before their villas.

From the Peristylum we ascend by a flight of steps into the Porticus (B), which is of the Corinthian Order. From this there were doors to two winding stairs, which led to the ground story, in order that the slaves might have access thither, without passing through any of the apartments.

(1) Plinius Junior, L. 2, Ep. 17; & L. 5, Ep. 6.

(2) Vitruvius, L. 6.

From the Porticus we enter the Vestibulum (C) which was commonly of a circular form (1); and in this Palace it seems to have been lighted from the roof. It was a sacred place, consecrated to the Gods, particularly to Vesta (2), (from whom it derived its name) to the Penates and Lares, and was adorned with niches and statues. Next to the Vestibulum is the Atrium (D), a spacious apartment, which the Ancients considered as essential to every great house. As the Vestibulum was sacred to the Gods, the Atrium was consecrated to their Ancestors, and adorned with their images, their arms, their trophies, and other ensigns of their military and civil honours (3). By this manner of distributing these apartments, the Ancients seem to have had it in view to express, first of all reverence for the Gods, who had the inspection of domestic life; and in the next place, to testify their respect for those Ancestors to whose virtues they were indebted for their grandeur. On each side of the door into the Atrium, lie two small rooms, one of which may have been the Cella Ostiarii (E), or Porter's Lodge, which Vitruvius tells us was common in houses of the Greeks, and was placed on one side of that passage by them called Thyrorion: the other was probably what the Ancients named a Tablinum (F), which Pliny mentions as a repository for the archives and records of the family, containing the history of the illustrious actions of their ancestors.

(1) Leo. Bap. Alberti, L. 9. C. 3.

(2) At Focus a flammis, et quod fovet omnia dictus
Qui tamen in primis ædibus ante fuit.

Hinc quoque Vestibulum dici reor, Inde precando
Dicimus, O Vesta quæ loca prima tences.

OVID. L. 6. Fastr.

(3) Apud majores in Atriis, Imagines hæ erant quæ spectarentur; non signa externorum artificium nec æra nec marmora. Plinius Senior, L. 35. C. 2. And a little lower he adds: Aliæ foris et circa limina Animorum ingentium imagines erant; affixis Gentium spoliis, quæ nec Emptori refringere liceret; triumphabantque etiam dominis mutatis ipsæ domus: et erat hæc stimulatio ingens, exprobrantibus tectis, quotidie imbellem dominum entrare in alienam triumphum.

The Poets often allude to this custom:

— Spolia illa tuis pendentia tectis.

VIRG. Æneid. L. 4.

Nec te decipiant veteris quinque Atria Caræ

Tolle tuos tecum, pauper Amator Avos.

OVID. L. 1. Amor. Elig. 8.

From

From the Atrium we proceed to the *Crypto Porticus* (G), a place of vast extent, intended for walking, and other exercises, which the Ancients reckoned of such importance, that the securing proper conveniences for them, was a chief object in all their buildings. This *Crypto Porticus*, like our modern galleries, was probably adorned with statues, pictures, and bas reliefs; and in this Palace serves likewise for giving access to several apartments, without passing through the rooms of parade, which were also defended by it, from the excessive heat of the south sun; a circumstance of so much consequence in hot climates, that we often find Vitruvius and Pliny attending to it with particular care.

If from the center of the *Crypto Porticus*, we look back to those parts of the Palace which we have already passed through, we may observe a striking instance of that gradation from less to greater, of which some connoisseurs are so fond, and which they distinguish by the name of a *Climax* in Architecture. The *Vestibulum* is larger and more lofty than the *Porticus*. The *Atrium* much exceeds the grandeur of the *Vestibulum*; and the *Crypto Porticus* may well be the last step in such a *Climax*, since it extended no less than 517 feet. We may likewise observe a remarkable diversity of form, as well as of dimensions, in these apartments which we have already viewed, and the same thing is conspicuous in the other parts of the Palace. This was a circumstance to which the Ancients were extremely attentive, and it seems to have had an happy effect, as it introduced into their buildings a variety, which, if it doth not constitute Beauty, at least greatly heightens it. Whereas Modern Architects, by paying too little regard to the example of the Ancients in this point, are apt to fatigue us with a dull succession of similar apartments.

Next to the *Alæ* of the *Atrium* (H) are two passages (I), which by the Romans were called *Andrones*, and by the Greeks *Mesaulæ*, from their situation between halls. There is access from them to several great rooms; they were lighted from the roof, and seem to have been contrived in order to prevent the noise of the *Atrienſes*, or Slaves in waiting in the *Atrium*, from reaching the adjacent apartments; and for that reason these apartments have not their entry immediately from the *Atrium*.

F

The

The first of these grand rooms is the Basilica (K), which Vitruvius mentions as common in all great houses, and directs that it should be spacious and magnificent in proportion to the dignity of the proprietor. Dioclesian's Architect has been careful to observe this precept; the Basilica here being such as suited the magnificence of an Emperor. This apartment was allotted for dramatic performances, recitals, music, and such like entertainments, and was lighted from the roof. On the other side of the Atrium, and corresponding to the Basilica, is the Egyptian Hall (L), which, according to Vitruvius, was nearly of the same form with the Basilica, and seems to have been lighted much in the same manner.

Adjoining to this is the Corinthian Hall (M), with regard to which the Architect has observed a rule of Vitruvius, by making the length of the room twice its breadth; and it is highly probable that he has likewise followed his direction, to light it from the North over the roofs of the Exedrae and Tetrastyle Halls, in the same manner as we find it often practised in the Baths at Rome.

Corresponding to the Corinthian Hall, and opposite to it, is the Cyzicene Hall (N), which in every particular resembles the former. These three halls, together with the Tetrastyles, or rooms of four columns (O), Vitruvius calls by the common name of Oeci. They were apartments for eating, and were generally of such a size, as to hold two Triclinia, or tables, with three beds each.

As the Oeci were employed in the same manner with our modern dining rooms, the Exedrae (P) served for the same uses with our withdrawing rooms. They were intended chiefly for conversation. Cicero calls them *Cellae ad Colloquendum*: They were placed near to the eating rooms, and are here lighted from the North.

Next to these we find the different apartments destined for bathing; a practice which the Ancients considered as essential to health; and with regard to all the apparatus necessary for that purpose, they displayed not only great elegance,

elegance, but the utmost luxury: Here we first enter an Apodyterium (Q), which was a room for undressing, and sometimes contained a Callida Piscina, or Lukewarm Bath (R), so large as to allow of swimming about in it. Next to this is the Cella Frigidaria (S), in which there was a Bapistiferium, or Cold Bath. Adjoining to this is the Unctuarium (T), or Repository for Unguents, with which the Ancients anointed themselves before their exercises. From this we go into the Cella Tepedaria (U), or Cella Media, so named from its middle degree of heat, and because it was a necessary preparation for the Laconicum, or Cella Caldaria (V), which was a bagnio for sweating in. All these different rooms in the Bathing Apartment were lighted from the roof.

On the other side of the Cella Media was a Spheristerium (W), a room allotted for the different exercises of the ball: this too must have been lighted from the roof. On the other side was the Emperor's Cubiculum Dormitorium, or Bed Chamber (X), which lay extremely convenient for the Bathing Apartment, and seems to have been particularly contrived for excluding light and noise. Pliny mentions an invention of the same kind in a bed chamber at his villa of Laurentinum.

Adjoining to it, and towards the Crypto Porticus, was what I take to have been a private Cænatio (Y), or Supping Room. This enjoyed the benefit of the setting sun, which for winter eating rooms Vitruvius recommends as requisite. On the other side of the Cubiculum Dormitorium lie three rooms, two of which, upon the authority of Pliny, I name Procatones, or Anti-chambers (Z), and the other Cella Liberti (a), or Freedmans Room.

Beyond the exterior Procatōri, and adjoining to the Arcade, are a number of vaults, which were probably employed as Cellæ Servorum (b), or Cells for the Slaves; though originally, and during the time that DIOCLESIAN held the empire, they might be used for lodging the Pretorian Soldiers.

In those Cellæ which lie next to the walls of the Bathing Apartments, were the Hypocauston (c); the Propnygeon (d); the Milliarium (e); and Cellæ
 " G Lignariæ;

Lignariæ (f); which were the names that the Ancients gave to the places and machinery employed for heating their baths, and other apartments.

For it is observable, that during all my researches among the ruins of this fabrick, I could not perceive the smallest vestige of a fire place. Though this was a circumstance to which I attended with particular care (1), fire places however the Ancients undoubtedly had, as Vitruvius mentions them, and directs the cornices of those rooms in which they were used, to be *puræ* or unenriched, that the dirtiness contracted by the smoke might be the more easily wiped off. There are many passages in the Roman authors (2) which prove that they used chimnies in their different apartments; and Palladio (3) and Barbaro assure us that, in their time, there were still to be seen the remains of fire places, with vents for carrying off the smoke, in three different parts of Italy: but at the same time it is no less evident, that the most common method of warming their rooms, especially in the houses of persons of distinction, was by conveying hot air to them through pipes fixed in the walls (4). In Pliny's description of his summer villa at Tuscum, he mentions a large *Cubiculum*, which in hot weather was sufficiently warmed by the sun, and when the weather was cloudy, it received a supply of warm air from the *Hypocaustum*: And in his letter concerning his winter villa at Laurentinum, he expressly takes notice of his bedchamber being warmed by hot air, which, without doubt, was also conveyed from the *Hypocaustum*. In the days of Vitruvius, chimnies seem to have

(1) In one of the highest walls of that building marked K, which I call the *Gynecum*, or apartments for matrons and young women, I discovered a chimney, which at first sight I took to be Ancient; but upon a nearer inspection, I found the construction to be undoubtedly of a later date, with a modern flue formed in the ancient wall.

(2) *Dissolve frigus Ligna super foco*
Large reponens.

HOR. L. 1. Carmen 9.

Nisi nos Vecina Trivici
Villa recipisset, Lacrimoso non sine fumo;
Udos cum foliis ramos urente Camino.

HOR. L. 1. Sat. 5.

(3) Palladio, L. 1. C. 27. Barbaro's Comment on his Italian Translation of Vit. L. 6. C. 10.

(4) Seneca tells us, *Epist.* 90. *Per impressos Parietibus Tubos per quos circumfundiretur Calor, qui una simul et summa feriret equaliter.*

been more common, but it is probable that as the passion for pomp, and the love of expence in building increased, the use of funnels in conveying and distributing hot air, might be gradually introduced, and the Romans might come to prefer this method, which had all the advantages of fire, without being subject to any of its inconveniencies. The use of hot baths, which became more frequent after the age of Vitruvius, contributed not a little to spread the fashion of warming the different apartments by means of flues.

The Baths, the Dormitorium, the Spheristorium, and other apartments which I have just now described, lie all in the west end of the Palace. There are not now any remains of the eastern part of the Imperial apartments beyond the Egyptian and Corinthian Halls. But as there is an exact uniformity in those rooms on each side of the Atrium, so far as they remain, I thought it most eligible not to indulge my fancy in forming any new conjecture, but simply to repeat the same distribution on this as on the other side; especially as a separate bathing apartment for the women, seems necessary to complete the conveniency and elegance of this building.

The Pinacotheca, or Room for Pictures, and the Bibliotheca, or Library, are apartments which Vitruvius mentions as common in all the great houses of the Romans: It would therefore surprise the reader, should he find no such rooms in the Palace of an Emperor, who was so remarkable for his love of the Fine Arts. But if we consider that noble Porticus or Gallery, which stretches along three sides of this building above the *Cellæ Servorum* and Arcades, extending no less than 1212 feet in length, and 31 feet in breadth, it is evident that sufficient space was left for apartments consecrated to those elegant Arts, of which *Dioclesian* was so great an admirer.

Towards the East (as we learn from Vitruvius) was the proper situation for the Bibliotheca; towards the North was the exposure most approved of for Pictures; and the West side may have been reserved for an *Horreum*, a room which Pliny mentions as a repository for statues, bas reliefs, and other curious productions of art. This gallery was divided by the three gates to the palace, and by the stairs on each side of them; but I found the communication had

H

been

been preserved by passages formed in the thickness of the walls over the gates, as may be seen by the general sections.

I come now to the Temples, which are placed in two areas adjoining to the palace, and are seen on each side of the Peristylum, through its rows of granite columns. Such attention to the honor and worship of the Gods, is suitable to the character which is given of **DIOCLESIAN** by ancient authors.

The square Temple (g), which was situated on the west of the Peristylum, was dedicated to *Æsculapius* (1). If we describe it according to the terms of ancient Architecture, it was *Prostylos*, *Tetrazylos*, and its intercolumniations were something more than *Systylos*; that is to say, the columns are all on one principal front; there are four of them on that front, and the intercolumniations are about two and a fifth diameters. The ascent to it was by a stair of fifteen steps, an uneven number being generally used in the Temples of the Ancients, that beginning to move with the right foot, they might of course place it first upon the uppermost step, in order to enter the Temple, a form which they accounted respectful in approaching a Deity (2). This Temple, like many other of the ancient ones, received no light but by the door. Beneath it are vaults of great strength; its roof is an arch adorned with sunk pannels of beautiful workmanship, and its walls are of a remarkable thickness. The Ancients were extremely solicitous to render their religious edifices as durable as possible, and the effects of this attention are now visible. This Temple still remains almost entire, and is at present employed by the Spalatrines as a Baptistry.

(1) Petrus Nicolinus, whose Manuscript is frequently cited by Farlatius, tells us: *Tertium quoddam sanum Basilicæ, e regione objacet ab occidente, quondam Æsculapio sacrum, Sacelli forma quadrata est, uno fornice Lapideo obtegetur mira Arte Celato, &c.* J. S. Tom. 1. p. 489. The history of Salona by Archidjocanus, is also cited by Farlatius to the same purpose.

(2) Vitruvius, L. 3. C. 3. Alberti, L. 1. C. 13.

On the other side of the Peristylum stands the Octagonal Temple (h), dedicated to Jupiter (1), who was worshipped by DIOCLESIAN with peculiar veneration, and in honor of whom he assumed the surname of Jovius. This Temple is of that kind, which Vitruvius calls Perypteros, i. e. surrounded with one row of columns, having an intercolumnation or space between them and the wall. Its intercolumnations are more than Areostyles, i. e. upwards of four diameters. It is lighted by an arched window over the door, and is vaulted beneath like that of Æsculapius. The dome over it is of bricks constructed in a very singular and ingenious manner, which, together with its walls, are of such solidity as to have resisted, almost unhurt, the injuries of so many ages; and I have even observed several of the tiles upon the roof still distinctly impressed with the Roman stamp, S. P. Q. R. It is at present the Cathedral Church of Spalatro, and is consecrated to the Virgin Mary, and St. Domnius.

This Temple is situated nearer to the Peristylum than the other; the reason of which seems to have been in order to gain space behind it for a Sacellum (i), where sacrifices might be offered on an altar looking towards the East, which, according to Vitruvius, was a circumstance not to be dispensed with.

The common opinion at Spalatro, which has been received without examination by several travellers, is, that there were four Temples within the precincts of the Palace. That apartment which for many reasons I have considered as the Vestibulum of the Palace, has hitherto been taken for one of these Temples. Of the fourth no vestige whatever is to be found, though I searched for it with great care. Were the controversy of much importance, it might easily be shewn, that there is no good authority for supposing there were formerly four Temples; but that in all probability none ever belonged to this Palace but the two which now remain.

(1) From *Farlati* we have these words of *Petrus Nicolinus*, relating to this Temple: *Quod autem scripsit platina, id olim Cibelis sanum fuisse, longe abest a Veritate, nemini quippe dubium esse potest, quin vetus et profana superstitio illud Jovi dedicaverit. Jovis simulachrum quod inibi collebatur adhuc extat, Visiturque in Museo gentis Capellæ, inter Patricias Venetorum familias Antiquæ et Conspiciuæ.* J. S. Tom. 1. p. 489.

In the description of this edifice, no mention has been made of a Culina, or kitchen of the Cellariæ, Apothecæ, and other offices which must necessarily have belonged to such a building. These, without doubt, were in proportion to the other parts of so great a work, and must have been placed in the half sunk or vaulted story. Part of these vaults now remain entire, and at present are used by the merchants for warehouses. They lie all along that side of the Palace next to the sea, and under the Crypto Porticus. There is also another vault which runs from South to North, under the Atrium, Vestibulum, and Porticus, which appears to have been a common entry to all the under-ground offices. These have been partly destroyed, and partly filled up; inasmuch that without great labor and expence in digging, it was not possible exactly to discover their disposition, or to form any plausible conjecture concerning their different uses. I attempted, however, at different times, to dig in various quarters of the Palace, and very probably might have made some useful discoveries, had not the repeated alarms and complaints of the inhabitants prevailed upon the Governor to send me the most positive orders to desist. I was therefore obliged, though with regret, to obey, and hastened to finish what remained uncompleted above ground, lest fresh suspicions should have prevented me from proceeding with that more essential part of my work.

All the buildings which we have hitherto surveyed, lie on the South side of that street which runs from the East to the West Gate. On the North of that street were situated two buildings (k) and (l), not much inferior in extent, nor probably in magnificence, to those we have already described: but by the injuries of time, and the depredations of the Spalatrines, these structures are reduced to a very ruinous condition; and though some walls still remain, which fix the form and dimensions of a few apartments, and show that they consisted of two stories, yet we have little to guide us in judging with regard to the arrangement and disposition of the whole. I have ventured, however, to form a plan of these buildings, by observing as carefully as possible such traces of the ancient divisions as are still visible. This I lay before the reader, who must rest satisfied with conjecture, where certainty cannot be attained. I suppose one of these buildings (k) to have been a *Gynæceum*, or an apartment allotted

allotted by the Ancients for the matrons and young women, and the other (1) I call the *Aulicorum Ædes*, or apartments for the different attendants on a court. The Jesuit Farlatus mentions such apartments as constituting part of this Palace; as also a *Domus Uxoris* (1), or apartment for the Empress; which last I have already placed in the east end of the Palace, corresponding to that of the Emperor.

The Towers are the only part of the Palace of which we have not taken a view. There are sixteen in all round this building, one on each angle, and four on each side, except on that towards the Adriatic. These Towers seem to have been intended for ornament, rather than for defence; it being impossible that a structure of this kind could ever be designed for a place of strength. We learn from Pliny, that towers were no uncommon ornament even in the villas of private persons. There were two of them in his villa at Laurentinum; and in them he places not only sleeping apartments, but a *Cænatio*, and *Triclinium*, a *Horreum*, and *Apotheca*. Here they might have been employed partly for the same, or perhaps for several other purposes.

Joannes Tomcus Marnovitiſ, an author whose words are produced by Farlatus (2), assures us, that in one of these Towers towards the South, was the burial-place of *DIOCLESIAN*, and that about two centuries ago, the body of the Emperor had been discovered there. He is even so minute as to describe the *Porphyry Sarcophagus* in which his remains were contained. If we may credit this authority, it appears that *DIOCLESIAN* chose to have his ashes deposited in the same favorite spot where he fixed his residence during the latter part of his life.

(1) Hic sũt Aulicis sedes, et domus Uxoris; et Matronis puellisqũe suum conclave, sive Gynæceum. *Illyricum Sacrum*, Tom. 2. p. 397.

(2) *Illyricum Sacrum*, Tom. 2. p. 414.

EXPLANATION

OF THE

PLATES.

WITH

Occasional Remarks on the Style of the Architecture.

Throughout this Work, all the GEOMETRICAL PLANS, ELEVATIONS, and SECTIONS, are figured in English Feet and Inches.

The Detail of the particular Orders and other Parts of the Buildings, are figured in Modules and Minutes; with a Scale of Feet and Inches annexed to each Plate.

PLATE I.

FRONTISPIECE.

PLATE II.

General Plan of the Town and Fortifications of Spalatro, shewing the Situation of the Ancient Palace of the Emperor **DIOCLESIAN**; also the great Bay and Harbour, the Lazaretto; the Mountain Margliano, the Fort of Grippe, the Suburbs, and the adjacent Grounds.

- | | |
|---|--|
| A. The Great Bay. | E. The Piazza, or Market Place of the present Town; the Houses of which are represented by single Lines, both within and without the Palace. |
| B. The Harbour. | F. Fortifications round the Town, built during the War of Candia. |
| C. Different Courts of the Lazaretto, in which the People trading from Turkey perform Quarantine, and where the Goods are purified. | G. The Fort of Grippe. |
| D. The Palace of DIOCLESIAN , which is shaded darker than the Modern Buildings. | H. The Suburb called the Borgia Luciaz. |

L

I. The

- I. The Suburb called the Borge Manus.
- K. The Suburb called the Borge Pozzo Bon, or Dobri.
- L. The Suburb called the Borge Grande.
- M. The Mountain Magliano, upon the Summit of which the Jews have their Burying Ground.

- N. A ruinous Fortification called Forte Botecelle.
- N.B. At the Top of this Plate are introduced some Parts of the Ancient Buildings of the Palace in Perspective.

P L A T E III.

View of the Town of Spalatro from the East.

- A. The Temple of Jupiter, now the Cathedral Church.
- B. A Modern Spire, built upon the Landing of the Stairs to the Temple of Jupiter, mostly composed of Fragments of Marble brought from Salona, and of Columns of Granite and other Materials, taken from the Palace. It now serves as a Steeple to the Cathedral Church.
- C.C. Antient Walls of the Palace.
- DDD. Modern Fortifications.
- EE. The Bay of Salona, which runs up into the Country three Miles, behind the Mountain Magliano.
- F. Lazaretto.
- G. The Harbour.
- H. Point of Land which forms the West Side of the Great Bay of Spalatro.
- I. The Mountain Margliana.
- K K K K. Islands in the Adriatic belonging to the Venetians.
- L. The Isthmus of Trau, anciently Tragurium, three Leagues from Spalatro; from which Place the Stones were brought to build the Walls of Dioclesian's Palace. These Quarries still remain open, and in them the People of Trau find Stones of the same Quality with those of which many Parts of the Palace are constructed.

P L A T E IV.

View of the Town of Spalatro from the South West.

- A. Temple of Jupiter.
- B. Steeple of the Cathedral Church.
- C. A Tower, formerly used as a Powder Magazine.
- DDD. Modern Fortifications.
- E. Wall of the Crypto Porticus, or Front of the Palace towards the Sea.
- FF. Ancient Towers at each End of the Crypto Porticus.
- G. The Lazaretto.
- H. The Harbour.
- II. Mills for making of Oil.
- K. Part of a Monastery.

P L A T E V.

General Plan of the Palace as it now remains.

Although in this Plate the Parts shaded with a dark Colour are what alone appear now above Ground, yet I have ventured to call this a Plan of the Palace as it remains; the Parts supplied in a lighter Colour being traced with the greatest Certainty,

either from the Foundations, or formed by joining the Lines of the corresponding Walls.

- A. The North or principal Gate, called still by its ancient Name, Porta Aurea.
- B. The Street leading to the Emperor's Apartments.

C. The

- C. The West Gate, called Porta Ferrea.
 - D. The East Gate, called Porta Ænea.
 - E. Street running from the East to the West Gate.
 - F. The Piazza, or Court of the Palace.
 - G. The Temple of Jupiter, now the Cathedral Church, consecrated to the Virgin Mary and St. Dominus.
 - H. The Temples of Æsculapius, now the Baptistry, consecrated to St. John the Baptist.
 - I. The Vestibule of the Palace.
 - K. Other Apartments of the Palace.
 - L. Bathing Apartments, &c.
 - M. Square and Octagon Towers.
 - N. Gallery to the South, or Crypto Porticus.
 - O. Vaulted Cells round the exterior Walls of the Palace.
 - P. A detached Building much ruined.
 - Q. Another detached Building.
 - R. Streets of Communication within the Palace.
 - S. Covered Arcades on each Side of the principal Streets.
 - T. Open Courts.
- N. B. As the Explanation of Plate VI. describes very fully the Names and Uses of the different Apartments of the Palace, to avoid Repetition, I have here referred by Letters only to the principal Parts of this Plan.

P L A T E VI.

General Plan of the Palace restored.

The Description of the general Plan, explaining the Manner of disposing the Apartments in the Houses of the Ancients, refers to this Plate.

- A. Peristylum, or Fore Court.
- B. Porticus, or Portico.
- C. Vestibulum, or Vestibule.
- D. Atrium, or Great Hall.
- E. Cella Ostiarii, or Porters Lodge.
- F. Tablinum, or Repository for Records.
- G. Crypto Porticus, or Gallery for Exercises and Walking.
- H. H. Alæ Atrii, or Wings of the Hall.
- I. I. Andrones, aut Mesaulæ, or Passages of Communication, and for preventing Noise.
- K. Basilica, or Room for Theatrical and Musical Entertainments.
- L. OEcos, aut Triclinium Egyptianum, or Egyptian Hall.
- M. OEcos, aut Triclinium Corinthium, or Corinthian Hall.
- N. OEcos, aut Triclinium Cyzicenum, or Cyzicene Hall.
- O. OEci, aut Triclinia Tetrastyli, or Rooms of four Columns.
- P. Exedrae, or Rooms for Conversation.
- Q. Apodyterium, or a Dressing and Undressing Room.
- R. Calida Piscina, or Lukewarm Bath.
- S. Cella Frigidaria cum Baptisterio, or Room containing a Cold Bath.
- T. Unctuarium, or Repository for Unguents.
- U. Cella Tepidaria, seu Cella Media, or Room of moderate Heat.
- V. Laconicum seu Cella Caldaria, or a Sweating Room or Bagnio.
- W. Spheristerium seu Coriceum, or Room for Exercise of the Ball, &c.
- X. Cubiculum Dormitorium DIOCLETIANI, or DIOCLETIAN'S Bed-Chamber.
- Y. Cenatio, or Supping Room.
- Z. Prociatores, or Anti-Chambers.
 - a. Cella Liberti, or Freedmans Room.
 - b. Cella Servorum, or Slaves Rooms.
 - c. Hypocauston, or Furnace.
 - d. Propnygeon aut Præfurnium, or Room before the Furnace.
 - e. Milliarium, or Spiral Pipe of Copper for heating Water for the Hot Bath.
 - f. Cella Lignariæ, or Vaults for Wood.
 - g. Templum Æsculapii, or Temple of Æsculapius.
 - h. Templum Jovis, or Temple of Jupiter.
 - i. Sacellum et Ara, or Chapel and Altar.
 - k. Gynecium, est Textrinum, seu Conclave, or Apartments for Matrons and Young Women.
 - l. Aulicorum Ædes, or Apartments for Courtiers.
 - m. Porta Aurea, or Golden Gate.
 - n. Porta Ferrea, or Iron Gate.
 - o. Porta Ænea, or Brazen Gate.

N. B. I have explained this Plate not only by the Terms used amongst the Ancients, but likewise by a Translation, such as they would admit of.

M

P L A T E

P L A T E VII.

View of the Crypto Porticus, or Front towards the Harbour.

- | | |
|--|--|
| <p>A. Ancient Wall of the Palace;</p> <p>B. Modern Wall built upon the Ancient Arcade; many of the Arches are likewise filled up with Modern Work.</p> | <p>C. Modern Houses built against the Wall of the Palace;</p> <p>D. Part of the Harbour.</p> <p>E. Part of the Town of Spalatro;</p> |
|--|--|

P L A T E VIII.

Geometrical Elevation of the Crypto Porticus, or South Wall of the Palace; and the Elevation of the same Wall as it now remains.

In this Plate I have given the Ancient Wall of the Crypto Porticus in its present State, to shew my Authority for the Restored Elevation. The Center Part over the Door into the Vaulted Story, is now entirely destroyed; which I have supplied, by following the Style of the two End Windows next the Towers, and from the Porticus to the Vestibulum (Vide Plate XXI.) In Imitation of which I have put a Triangular Pe-

diment, as I think it extremely probable the Architect to this Palace would chuse to distinguish the Center of so long a Building, and the Vacuity answers precisely to this Decoration.

The Whole of the Arcade and Basement Story of this Front, are built of the beautiful Free-stone from Tragurium, which appears little inferior to Marble. The Columns of the two End Windows are of Granite.

P L A T E IX.

Elevation and Profile of one Arch of the Crypto Porticus.

- A. Elevation of the Arch.
- B. Profile of the same:

The Columns which divide the Arches, project one Half of their Diameter, and are of an uncommon Kind; they approach most to the Doric, both in their Mouldings and Proportions, being exactly Eight Diameters of the Column in Height. No Signs remain of there having been any Enrichments upon the Vase of the

Capitals, which, from the Fillet of the Cavetto at Top, to the Collorino, is one Diameter of the Column. The String at the Bottom, which breaks like a Console under each Column, runs all along from Tower to Tower. The Dentil Cornice, with two plain Fascias under it, seems to have been kept simple, to correspond with the general State of the Order; and the Whole is far from having a bad Effect.

P L A T E

P L A T E X.

Geometrical Elevation of the Porta Ænea, or East Wall of the Palace.

- A. Porta Ænea. C. Square Towers of the Palace.
B B. Octagon Towers on each Side of the Gate.

Elevation of the same as it now remains.

- D. Modern Building, where the Ancient Wall is destroyed.
E. Square Tower, which had been greatly decayed, and afterwards repaired in this Form.
Although but little of the Ancient Porta Ænea remains, by which I could form a proper Conjecture of its ancient State, yet I was enabled to make out the Whole from the Remains of the Porta Ferrea on the West Side of the Palace (see Plate XVII.), which is almost perfectly entire, and seems to be precisely similar to this Gate in those Parts that still remain.

P L A T E XI.

Geometrical Elevation of the Porta Aurea, or North Wall of the Palace.

Elevation of the same Wall as it now remains.

P L A T E XII.

View of the Porta Aurea.

- A. Gate and Arch now built up by the Spalatrines. D. Part of one of the Octagon Towers.
B. Granite Columns supported by Consoles, (see Plates XV. and XVI.) E. Windows which give Light to a Nunnery, of which this Gate now forms one of the Walls.
C. Niches for Statues.

P L A T E XIII.

Geometrical Elevation of the Porta Aurea and Octagon Towers.

- A. The principal Gate, divided from a Semicular Opening over it, by a flat Arch of a particular Construction, which remains perfectly entire.
B. Octagon Tower on the East Side of the Gate, shewing the Outside Wall.
C. Octagon Tower on the West Side of the Gate, shewing Part of the Inside Wall, with the Doors from the Ground Story and Gallery above, and the Trusses for carrying the Timbers of the Floor and Roof.
This Gate is more ornamented than the other Gates of the Palace, it being the principal Entry to the Emperor's Apartment, and fronting the Porticus of the Vestibulum. The lower Niches

N

on

on each Side of the Gate, as well as the Arch
over it, inroach too much upon the superior Or-
der, and do not seem to add to the Beauty of
the Building, either by their Form or Situation.
It is not any Part to enquire into the Reasons

that might induce DIOCESIAN'S Architect to
make this Disposition, which appears to me
much inferior to many other Parts of the Build-
ing.

P L A T E XIV.

Impost Cornice and Archivolt of the Porta Aurea.

- A. Part of the Impost Cornice.
B. Part of the Archivolt.

- C. Console and Part of the Cill of the Niches of the
Porta Aurea.

P L A T E XV.

Consoles which support the Columns of the Porta Aurea.

- A. Fronts of the Consoles.

- B. Profiles of the Consoles.

P L A T E XVI.

Impost and Archivolt of the Upper Niches of the Porta Aurea.

- A. Impost.
B. Junction of Part of two Archivolts.

- C. One of the Consoles in Perspective.

P L A T E XVII.

View of the Porta Ferrea.

- A. The Porta Ferrea, or Iron Gate.
B. One of the Ancient Octagonal Towers.
C. Guard-Room formed of Antique Columns, and
other Fragments of Marble taken from the Palace.

- D. Court of Justice.
E. The Piazza, or Market-Place of the present Town.

P L A T E XVIII.

General Section of the Palace from South to North.

- A. Octagon Tower of the Porta Aurea.
B. The Porta Aurea.
C. C. Exterior Wall of the Palace.

- D. D. Apartments for Courtiers.
E. Porta Ænea.
F. Temple of Jupiter.

- G. Peristylum

- | | |
|---|--|
| G. Peristylum, or Fore Court of the Palace. | L. The Crypto Porticus. |
| H. The Porticus of the Vestibulum. | M. Square Tower at one End of the Crypto Porticus. |
| I. The Vestibulum. | NN. Vaulted Story under the Apartments of the Emperor. |
| K. Part of the Walls of the Emperor's Apartments. | |

P L A T E XIX.

General Section of the Palace from East to West.

- | | |
|--|---|
| A. Octagon Tower of the Porta Aenea. | I. Vaults under the Temple. |
| B. Porta Aenea. | K. K. Gates to the Streets of Communication within the Palace. |
| CCC. Exterior Wall of the Crypto Porticus. | L. Porta Ferrea. |
| D. Infine of the Temple of Jupiter. | M. Octagon Tower of the Porta Ferrea. |
| E. Vault under the Temple. | NNNN. Passages in the Walls of the Gateways which communicate with the Galleries round three Sides of the Palace. |
| FF. Remaining Walls of the Exedrae. | |
| G. Porticus and Vestibulum of the Palace. | |
| H. Temple of Aesculapius. | |

P L A T E XX.

View of the Peristylum of the Palace.

- | | |
|--|--|
| A. Front of the Vestibulum. | II. Arches of the Covered Arcades of the Street from the East to the West Gate, now converted into Shops: |
| B. Part of the Spire of the Cathedral Church. | In the principal Front of Dioclesian's Baths at Rome, published from the Drawings of Palladio by Lord Burlington, there is an Arcade, supported by Columns, with Archivolts from Column to Column, exactly similar to those of the Peristylum of this Palace. As that Part of these Baths have been destroyed since Palladio's Time, I am obliged to quote his Authority, instead of appealing to the Original itself. |
| C. C. Collonades on each Side of the Peristylum. | |
| D. Part of the Temple of Jupiter. | |
| E. Gothic Sepulchre. | |
| F. Marble Lattice and recently placed between the Columns of the Peristylum, dividing it from the Courts of the Temples. | |
| GG. Two modern Chapels built within the Porticus of the Vestibulum. | |
| H. Sphinx formerly placed within the Temple of Jupiter. | |

P L A T E XXI.

Elevation of the Portico to the Vestibulum.

The Corinthian Columns of this Porticus, as well as those on both Sides of the Peristylum, are of Oriental Granite, and the Entablatures and Capitals of Statuary Marble. The Arch over the

two Center Columns of the Porticus is somewhat singular, though we find almost a similar Instance in Mr. Wood's BALBEC, Plate VII. This Form may be liable to Objection, as deviating from

from the pure Simplicity of the Ancients; yet it appears to have been from something of this Kind that Palladio, and other Architects of his

Time, have adopted the Modern Venetian Window, which bears a great Resemblance to this Porticus of Dioclesian's Palace.

P L A T E XXII.

Order of the Portico to the Vestibulum, in the Peristylum.

P L A T E XXIII.

View of the Inside of the Vestibulum.

- A. Door from the Porticus.
- B. Part of the Arch of the Vaulted Story.
- C. A Modern Building within the Vestibulum.

The Inside of the Vestibulum was built of Brick, and covered over with a hard Cement for receiving an Incrustation of Marble, in the same Manner as the Walls of some of the Apartments in the Baths of this Emperor at Rome; and

also of those of Caracalla, where there still remain some Parts finished in that Way. The Dome is also Arched with Bricks, but so much decayed that it is not now possible to discover in what Manner it has been adorned.

The Architraves, Friezes, and Cornices are all of White Marble.

P L A T E XXIV.

Door of the Vestibulum.

P L A T E XXV.

Part of the Door of the Vestibulum to a larger Scale.

P L A T E XXVI.

Plan of the Temple of Jupiter.

- A. Circular Niches of the Temple.
- B. Square Niches.
- C. Stairs of the Temple;

- D. Door of the Temple;
- E. Covered Collonade round the Temple;

P L A T E XXVII.

Side View of the Temple of Jupiter.

- A. Pedestal which supports the Columns round the Temple.

- B. Columns of Granite as they now remain;
- C. Part of the Entablature over the Columns;

D. Wall

D. Wall of the Temple:

E. First Story of the Spire built upon the Landing of the Stairs.

P L A T E XXVIII.

View of the Entry to the Temple of Jupiter.

A. Door of the Temple, (see Plates XXXI. and XXXII.)

B. Columns that go round the Outside of the Temple.

C. Part of the Entablature and Soffit of the Colonnade.

D. Arch which supports the Modern Spire.

E. Gothic Sepulchre.

F F. Ancient Sarcophagi.

P L A T E XXIX.

Geometrical Elevation of the Temple of Jupiter.

A. The Stairs.

B. Door of the Temple.

C. Arched Window.

It is extremely probable that the Arched Window to this Temple has been opened since the Time of *Dioclesian*, Light being seldom admitted, (except by the Door) into the Temples of the Ancients. The Construction of the Arch itself appeared to me more modern than the other Parts of the Temple, and seems greatly to strengthen this Conjecture.

In restoring this Temple, I have placed a Statue over each Column, as I found by the Cramps that remain in the Plinth over the Entablature, that it had been originally decorated in that Manner, though now there are none of the Figures remaining. The Grandeur of the Colonnade, which is *Arcofytos*, is in some Degree impaired by the double Pedestal, which goes round the Temple; I should have suspected that Necessity had obliged *Dioclesian's* Architect to use this Method of adding Height to Columns which the Emperor had commissioned from Greece, or perhaps transported from Italy. But upon examining that Building in *Palmyra*, Plate XLV. which, from the Latin Inscription, is thought to be the Work of *Dioclesian*, I find that the Architect uses a double Pedestal to the Columns there, exactly in the same Manner as in this Temple.

Nor is it less remarkable, that at both Places the Frises over the Doors are often left out; and in some of the Entablatures the Architraves are so broad, as almost to equal the Height of both Frise and Cornice. Besides these Circumstances there is so great a Similarity in some of the Members and Enrichments of both these Buildings, that it serves, in my Opinion, as an additional Proof of the Justice of Mr. Wood's Hypothesis in ascribing that Temple to our Emperor.

Having made particular Mention of the Roof of this Temple in the Description of the General Plan, (Page 15) I shall only observe, that the Form of a pointed Roof in Temples of this Kind, is uncommon in the ancient Buildings of the Romans, as the Flat Dome seems to have been their more favorite Form: But having found the Roman Stamp upon the Tiles that still cover it, there was no Room left to doubt its Antiquity.

The Stairs to the Temple seem to me very defective, by being so much confined between the large Pedestals on each Side. Had they extended the whole Width of the four Columns in Front, it would undoubtedly have added greatly to the magnificence of the Building. The Walls and Pedestal of the Temple are of Stone from *Tragurium*; the Columns of Granite; the Capitals and Entablature of White Marble.

P

P L A T E

P L A T E XXX.

Exterior Order of the Temple of Jupiter.

P L A T E XXXI.

Door of the Temple of Jupiter.

P L A T E XXXII.

Part of the Door of the Temple to a larger Scale.

The Dressing of this Door, though uncommon, has a bold and pleasing Effect. The Ornament upon the Swelling Moulding is of very fine Workmanship. The Modillions in the Cornice are not perpendicular over the Trusses, and of-

fend the Eye greatly. The Angular Modillion, which is to be found in many Parts of this Palace, as well as in other Buildings of the Ancients, seems in this Door to be no additional Ornament.

P L A T E XXXIII.

View of the Inside of the Temple of Jupiter.

A. Door of the Temple.

B. Window over it.

C. One of the Circular Niches.

D. One of the Square Niches.

P L A T E XXXIV.

Geometrical Section of the Temple of Jupiter.

A. Inside of the Dome, shewing the Construction of the Brickwork.

B. Entablature of the Second Order, (see Plate XXXVI.)

C. A Frieze which goes round the Temple, (see Plates XXXVIII. and XXXIX.)

D. Entablature of the First Order, (see Plate XXXV.)

E. Impost Cornice of the Niches, (see Plate XXXVII.)

F. Door of the Temple.

G. Arched Window over the Door.

H. Section through the Portico to the Temple.

I. Pedestal and Section of the Stairs to the Temple.

K. Section through the Collonade which surrounds the Temple.

The

The Shafts of the Columns of the First or Corinthian Order within the Temple, are of Oriental Granite of one Stone. The Capitals and Bases of the Columns, and all the Entablature, are of Parian Marble. Behind the Corinthian Capitals of the Columns, there are Pilaster Capitals, with a very small Projection, of the same Marble with the Capitals of the Columns: But no Pilaster is carried down, nor no Base shewn, which, however defective it may have been, makes me think that nothing more than the Capitals was ever intended.

The Shafts of the Columns of the second Order, which is Composite, are alternately of Verde Antique, or Ancient Green Marble, and Por-

phyry, of one Piece. The Capitals and Entablature are also of Parian Marble. Behind each Column in the Second Order is a Pilaster, which projects One Fourth of its Diameter. The Shafts of these Pilasters are of the same Stone as the Walls of the Temple, and worked solid with the Wall; but the Capitals are of the same Marble with that of the Columns. It is very remarkable that this Order had no Bases, either to the Columns or Pilasters, like the Grecian Doric; and the Height of the Column and Capital does not exceed Seven Diameters, which is three Diameters less than is allowed to this Order in most of the other Works of the Ancients.

P L A T E XXXV.

First Interior Order of the Temple of Jupiter.

P L A T E XXXVI.

Second Interior Order of the Temple of Jupiter.

P L A T E XXXVII.

A. Outside Entablature at the Top of the Temple of Jupiter. B. Impost and Archivolt of the Interior Niches;

P L A T E XXXVIII.

Bas Relief which forms a Frise in the Inside of the Temple of Jupiter.

P L A T E XXXIX.

Other Bas Reliefs, being Part of the same Frise.

Q

P L A T E

P L A T E XL.

Plan of the Temple of Æsculapius.

- | | |
|--|---|
| A. The Body of the Cell of the Temple, | C. The Portico. |
| B. The Door, | D. The Stairs partly sunk under Ground. |

P L A T E XLI.

View of the Temple of Æsculapius.

- | | |
|--|---|
| A. The Back Wall of the Pediment. | E. A Marble Urn, the particular Sculptures on which are delineated, Plate LI. |
| B. Architrave that went round the Inside of the Portico. | F. Sarcophagus placed by the Door of the Temple |
| C. Door of the Temple, (see Plate XLVI.) | G. Modern Buildings. |
| D. Large Blocks of Stone, forming the Dado of the Pedestal that supports the Temple. | |

P L A T E XLII.

Another View of the Temple of Æsculapius.

- | | |
|--|----------------------|
| A. Part of the Stairs leading to the Temple. | C. Modern Buildings. |
| B. The other Side of the Marble Urn. | |

P L A T E XLIII.

Lateral Elevation of the Temple of Æsculapius.

The Walls of this Temple are built of Freestone; and of very fine Workmanship: The Frise is very elegant, of which I have given the exact Representation, Plate L.

The Roof is finished like an Arch on the Outside, as well as within; but the Pediment at the West

End of the Temple, which still remains entire, finishes in a Triangular Form, which was my Authority for finishing the East End, where the Portico was, in the same Manner, though that is now entirely destroyed, as is shewn by the preceding Views.

P L A T E XLIV.

Section of the Temple of Æsculapius.

I was enabled to fix pretty nearly the Distance betwixt the Pilafter and Column of the Portico,

both in this Section and in the last Plate, by observing the Vacuity left by one of the Plinths of the

the Columns which was removed before I went to Spalatro. I for this reason have marked that Column of a darker Colour in the Plan, to show where the Plinth stood, the Center of which

Space I have made the Center of the Column.

The Whole of the Inside of this Temple is perfectly entire, and of very good Workmanship.

P L A T E XLV.

Door of the Temple of Æsculapius.

P L A T E XLVI.

A. Part of the Door of the Temple to a larger Scale.

If we abstract from the Defect of the angular Modillions in this Door, some of the other Parts of it are very fine. It may indeed be objected with Reason, that it is too much ornamented for an Outside Door; yet we have many Examples in PALMYRA and BALBEC, of Outside Doors very

much loaded with Ornament. The particular Enrichments of this Door are so finely executed, that they afforded me the highest Satisfaction; and by Means of the projecting Portico, the smallest Parts have remained unhurt to this Day.

B. Part of the Soffit of the Cornice.

P L A T E XLVII.

Exterior Order of the Temple of Æsculapius.

The Pilafter Capital of this Temple, and indeed all the Capitals throughout this Palace, are ruffled more in the Grecian than the Roman Style, which I have been very careful to imitate. It is more than probable, that DIOCLESIAN, who had been so often in that Country, brought his

Artificers from Greece to Spalatro, with an Intention to vary the Execution of his Orders of Architecture in this Palace, from those he had executed at his Baths at Rome, which are extremely different both in their Formation and Execution.

P L A T E XLVIII.

A. Interior Frieze and Cornice of the Temple of Æsculapius.

B. Soffit of the above Frieze and Cornice.

The Internal Angular Modillion in this Cornice is

very remarkable: I do not remember to have met with any other Instance of it in the Works of the Ancients.

P L A T E XLIX.

A. Pannels of the Arched Ceiling of the Temple of Æsculapius.

B. Profile of the Mouldings.

C. Capital and Pilafter in the Angle of the Peristylum.

R

P L A T E

P L A T E L.

Exterior Frise of the Temple of Æsculapius.

P L A T E LI.

Bas-Relief of an Urn near the Temple of Æsculapius.

P L A T E LII.

Fragment of the Architrave of a Door to the Crypto Porticus.

Enriched Mouldings round the Octagon Towers.

P L A T E LIII.

Fragment of a Bas Relief at Spalatro.

It is Pity that this Bas Relief was so much destroyed when I saw it, as that Part which re-

mains, representing some Bacchanalian Ceremony, is of exquisite Sculpture.

P L A T E LIV.

Bas Relief in the House of Count Jeremiah, at Spalatro.

P L A T E LV.

View of a Sphynx, which was anciently in the Temple of Jupiter.

P L A T E LVI.

Another View of the same Sphynx.

P L A T E LVII.

Bas Relief in the Church of St. Felix, at Spalatro.

P L A T E

P L A T E LVIII.

Bas Relief, representing a Combat with the Centaurs.

P L A T E LIX.

Bas Relief found incrufted in the Spire of the Cathedral Church.

P L A T E LX.

- A. View of a Sphinx, with Hieroglyphics.
B. Front View of the same Sphinx.

C. Another View of the same Sphinx.

P L A T E LXI.

View of the Aqueduct which conveyed Water from Salona to the Palace.


This Aqueduct is vulgarly supposed to have been a Highway leading from Salona to Spalatro: But besides the Remains of the Conduit for Water, which is yet observable in many Places, it is too narrow ever to have served for any other Purpose than that of an Aqueduct, as it is not above Eight Feet wide over the Walls. The Nature of the Soil itself was sufficient to convince me of the Absurdity of the common Hypothesis, as the Aqueduct is built either on a hard Rock, or firm Gravel, which rendered any

artificial Highway entirely useless between Salona and the Palace.

* Vischer, in his *Architecture Historique*, mentions this Aqueduct as conveying Water from the River Jader, which has its Source in the Mountains two Miles above Salona. In this I think he is right; but cannot agree with his Supposition of there having been a high Road over it; which he seems to have borrowed without Examination, from the common Tradition prevalent among the Spalatrines.

* *L'Architecture Historique*, L. 2. Tab. 10 and 11.







GENERAL PLAN
of the *TOWN* and *FORTIFICATIONS* of
S P A L A T R O,
Shewing the Situation of the Ancient Palace
of the
EMPEROR DIOCLESIAN
Also the Great Bay and Harbour; The Lazaretto
the Mountain Margliano, the Fort of
Grippe, The Suburbs & the
Adjacent Grounds.



Back of
Foldout
Not Imaged



View of the Town of Spalatro from the



East.

Back of
Foldout
Not Imaged

Back of
Foldout
Not Imaged




View of the Town of Spalatro from the South Sea




Back of
Foldout
Not Imaged



Hand (Patent 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100)







General Plan of the Palace as it now Remains

Scale 1/4 inch = 10 feet






Small Central 370 feet.



North 608 feet

East

West




General Plan of the Palace Restored

(Scale: 1/100000)


Scale of Feet


J. P. B. 1818





View of the Egyptian Portico or Street towards the Harbour







Geo






Symmetrical Elevation of the Crypto Porticus or South Wall of the Palace,



Elevation of the Same Wall as it now Remains

Back of
Foldout
Not Imaged

Elevation and Profile of one Arch of the Crypto Porticus




Back of
Foldout
Not Imaged

Geometrical Elevation of the Porta Nuova or



Total Extent 697 Feet




Elevation of the Same Wall as it now Remains


East Wall of the Palace

Plate 8



Plate 8





Geometrical Elevation of the Port



Total Length 370

Elevation of the Same



Scale of Feet

Aurea or North Wall of the Palace



Wall as it now Remains





H. Kuhn del.



View of the Porta Aurea


J. Smith del.





Geometrical Elevation of the Portico


— — — — —




la. Aphaia and Propylaea Towers



Back of
Foldout
Not Imaged




General Section



of the Palace from South to North

Back of
Foldout
Not Imaged


Impost Cornice and Archivolt of the Porta Aurea




Console and part of the Cell of the Niches of the Porta Aurea

Scale of feet

Consoles which support the Columns of the Porta Nuova



Impost and Archivolt of the Upper Vices of the Porta Aurea




One of the Consoles in Perspective




Piazza della Porta - Ferrara






General Section of the S.



Palace from East to West





View of the Peristyle



of the Palace?




Total Extent 32 8 1/2

Scale of Feet

Elevation of the Portico to the Vestibulum

Order of the Portico to the Vestibulum in the Peristylum




Scale of Feet

Scale of Feet




View of the Inside of the Testabulum

Door of the Vestibulum




Part of the Door of the Vestibulum to a Larger Stile



Scale of Feet

Each inch



Plan of the Temple of Jupiter





Side View of the Temple of Jupiter.

PLATE XXXIII



View of the Entry to the Temple of Jupiter






Geometrical Elevation of the



Temple of Jupiter

Exterior Order of the Temple of Jupiter




Scale of Feet

Door of the Temple of Jupiter



Part of the Door of the Temple to a Larger Scale




Height	Fig.
1	32
2	33
3	34
4	35
5	36
6	37
7	38
8	39
9	40
10	41
11	42
12	43
13	44
14	45
15	46
16	47
17	48
18	49
19	50
20	51
21	52
22	53
23	54
24	55
25	56
26	57
27	58
28	59
29	60
30	61
31	62
32	63
33	64
34	65
35	66
36	67
37	68
38	69
39	70
40	71
41	72
42	73
43	74
44	75
45	76
46	77
47	78
48	79
49	80
50	81
51	82
52	83
53	84
54	85
55	86
56	87
57	88
58	89
59	90
60	91
61	92
62	93
63	94
64	95
65	96
66	97
67	98
68	99
69	100

Scale of Feet



View of the Inside of the Temple of Jupiter






Temple of Jupiter

Scale of Feet


H. Koster sculp.

First Interior Order of the Temple of Jupiter



Scale of Feet


Second • Interior Order of the • Temple of Jupiter



Scale of Feet

1/2 inch = 1 foot

Outside Entablature & Top of the Temple of Jupiter



Impost and Archivolt of the Interior Niches


and up



Bas Reliefs which form a Frieze in the Inside of the Temple of Jupiter




E. Bouché del.




Other Bas Reliefs being part of the same Frieze



E. Bouché del.




Plan of the Temple of Esculapius




View of the Temple of Aesculapius



Another View of the Temple of Vesta, &c.




Exterior Elevation of the Temple of Hercules
 1. 1/2 scale in length




Section of the Temple of Bel at Babylon


Door of the Temple of Esculapius



Part of the Door of the Temple to a Larger Scale




Part of the Soffit of the Cornice




Scale of Feet

Exterior Order of the Temple of Esculapius




Interior Frise and Cornice of the Temple of Hercules



Left of the above Frege and Cornice

Plat. XLIX
Panels of the Arched ceiling of the Temple of Herculaneum



Capital and Plaster in the Angle of the Peristylum



Plate I.

Exterior Frieze of the Temple of Hercules




Plate LI



Bas Reliefs of an Uln near the Temple of Hercules

Fragment of the Architecture of a Door to the Crypto Portico



Enriched Mouldings round the Octagon Towers



Fragment of a Bas-relief at Spalatro



Bas Relief in the House of Count Jeremiah at Spilatro

View of a Sphinx which was anciently in the Temple of Jupiter



Another View of the Same Sphinx






Bas Relief in the Church of S. Felice at Spalatro




Bas Relief representing a Combat with the Centaurs



Bas Relief found encastré in the Spire of the Cathedral Church

View of a Spina with Microglyphics

Plat LX



Front view of the same Spina



Another son of the same, John



Dr. Darlezz's Sculpt.



-View of the Aqueduct which conveyed Water from Salinas to the Seville

HILL LIBRARY
St. Paul, MN.
RELEASED





Special 84-B
Owens 32267
NA
335
576
A19
1764
C3 THE GUTTY CENTER
LIBRARY

